

## **BEAM FLOORING TO EC2**

Version 14.28

Job title : New House, Chadlington

By: PTC

Tel: 01636 832000

Date: 26/04/18

Floor system : Beam & Block , Floor case : IJ1

Beam ref: BT02. 125 mm wide (73 mm at top) x 150 mm deep. 4 no. wires. No. of beams = 1.

Block type: Aggregate infill block 440 mm wide. Density = 1500 kg/cu.m.

Floor case width = 525 mm. ==I==

Exposure type XC1 for EC2 category: 'Inside enclosed buildings' gives design class with permissible tension.

Type of floor loading = Domestic.

Effective span = 3.400 m. Clear span = 3.300 m.

Alternative point load checked: 2 kN at mid span

			Use maximum of EC1 equation 6.10(a) or						0(a) or (b)		
LOADING		kN/m <sup>2</sup>		:h	Service	Ultimate 6.10(a)				Ultimate 6.10(b)	
			(m)		(kN/m)			(kN/m)			(kN/m)
Self weight of beam, block and infil	1.86	х	0.53	=	0.98	Х	1.35	1.32	х	1.25	1.22
Self weight of structural topping	0.00	Х	0.53	=	0.00	Х	1.35	0.00	х	1.25	0.00
Finishes other than structural topping	2.70	Х	0.53	=	1.42	Х	1.35	1.91	х	1.25	1.77
Partitions (allow)	0.00	Х	0.53	=	0.00	Х	1.35	0.00	х	1.25	0.00
Superimposed live	1.50	Х	0.53	=	0.79	Х	1.05	0.83	Х	1.50	1.18
Total	6.06				3.18			4.06			4.17

RESULTS	M service	M ultimate	LHS shear	RHS shear	Max V <sub>Ed</sub> / V <sub>Rd</sub>	Total Deflection	Movement
	(kNm)	(kNm)	(kN)	(kN)	(ratio)	(mm)	(mm)
Actual	4.60	6.02	7.09	7.09	0.33	4.8	1.0
Limit	5.99	8.44	20.29	20.29	1	13.6*	9.7**

<sup>\*</sup>span/250 \*\*span/350 \*\* Finishes = Non-brittle finishes

Flexurally cracked shear occurs at x = 1.088 and 2.312 m from LHS

Shear force PASS
Alternative point load PASS

Natural frequency = 8.9 (Hz) Minimum value = 4.0 (Hz)

Crack width = 0.000 (mm) Limiting value = 0.2 mm

PASS

PASS

Service moment PASS
Ultimate moment PASS
Deflection PASS

Curltailment length

\* \* \* Design satisfactory \* \* \* (max. ratio actual / limit = 0.86)

Sheet 1 of 1