

BEAM FLOORING TO EC2

Version 14.28

Job title : New House, Chadlington

By:PTC

Tel: 01636 832000

z into i itom i iodoo, ondamigio.

Calc ref: 4

Date: 26/04/18

Floor system : Beam & Block , Floor case : RDJ8

Beam ref : RD09. 215 mm wide (165 mm at top) x 150 mm deep. 9 no. wires. No. of beams = 2.

Block type: Aggregate infill block 440 mm wide. Density = 1500 kg/cu.m.

Job ref : 68361

Floor case width = 716 mm. ==II=

Exposure type XC1 for EC2 category: 'Inside enclosed buildings' gives design class with permissible tension.

Type of floor loading = Domestic.

Effective span = 6.050 m. Clear span = 5.950 m.

Alternative point load checked: 2 kN at mid span

			Use maximum of EC1 equation 6.10(a) or					0(a) or (b)			
LOADING	kN/m ²		Width		Service	Ultimate 6.10(a)				Ultimate 6.10(b)	
			(m)		(kN/m)			(kN/m)			(kN/m)
Self weight of beam, block and infil	2.66	Х	0.72	=	1.90	Х	1.35	2.57	х	1.25	2.38
Self weight of structural topping	0.00	Х	0.72	=	0.00	Х	1.35	0.00	х	1.25	0.00
Finishes other than structural topping	2.70	Х	0.72	=	1.93	Х	1.35	2.61	х	1.25	2.41
Partitions (allow)	0.00	Х	0.72	=	0.00	Х	1.35	0.00	х	1.25	0.00
Superimposed live	1.50	Х	0.72	=	1.07	Х	1.05	1.13	х	1.50	1.61
Total	6.86				4.91			6.30			6.40

RESULTS	M service	M ultimate	LHS shear	RHS shear	Max V _{Ed} / V _{Rd}	Total Deflection	Movement
	(kNm)	(kNm)	(kN)	(kN)	(ratio)	(mm)	(mm)
Actual	22.46	29.28	19.36	19.36	0.23	13.4	8.3
Limit	24.90	40.60	82.58	82.58	1	24.2*	17.3**

^{*}span/250 **span/350 ** Finishes = Non-brittle finishes

Flexurally cracked shear occurs at x = 1.331 and 4.719 m from LHS

Shear force PASS
Alternative point load PASS

Natural frequency = 4.4 (Hz) Minimum value = 4.0 (Hz)

Crack width = 0.009 (mm) Limiting value = 0.2 mm

PASS

PASS

Service moment PASS
Ultimate moment PASS
Deflection PASS

Curltailment length

Sheet 1 of 1

^{* * *} Design satisfactory * * * (max. ratio actual / limit = 0.91)